

Resurvey of South Bdy. of T. 3 N., R. 37 E.

Chains	
3.10	Foot; branch of Burk creek, 8 lks. wide, runs N.85°W., ascend steep hill, bears N.W. and S.E.
14.25	Steep, heavily timbered slope N.
17.50	Shallow ravine, course N.10°E., thence hill bears N.W. and S.E.
25.00	Top of rise on ridge N. of bald point; descend, bears N.E. and S.W.
29.25	Down steep bank.
30.60	Rill, 1 lk. wide, runs N.10°W., thence over point.
32.50	Top of rise and descend.
34.75	Foot; rill, 1 lk. wide, runs N.30°E.; ascend steep, grassy hill through scattering timber and patches of dense undergrowth, bears N.20°E. and S.20°W.
40.00	A point, 500 feet above the sec. cor. and set a basalt stone, 15x10x4 ins., 10 ins. in the ground, for $\frac{1}{4}$ sec. cor. S. bdy. sec. 35, marked $\frac{1}{4}$ on N. face, from which, A fir, 18 ins. diam., bears N.20°E., 96 lks. dist., marked $\frac{1}{4}$ S 35 B T. The old $\frac{1}{4}$ sec. cor., post missing, bears N.75°W., 1 ch. 10 lks. dist., as determined by witness tree. A fir, 12 ins. diam., marked and witnessed as described by the surveyor general. I destroy all traces of this old $\frac{1}{4}$ sec. cor.
49.00	Top of narrow ridge, point N.30°E; descend through heavy timber and undergrowth, bears N.E. and S.W.
54.75	Ascend; bears N.W. and S.E.
57.50	Leave timber and undergrowth, bears N.W. and S.E.
59.75	Top of N.E. brow of mountain; thence gradual ascent through scattering timber and undergrowth.
70.00	Descend gradually from summit of divide.
78.25	Buck Mountain trail, bears N.60°W. and S.60°E.
80.00	A point 300 feet above the $\frac{1}{4}$ sec. cor and set a basalt stone, 20x15x8 ins., 4 ins. in the ground (strike bed rock and place mound of stones firmly about cor.) for cor. of secs. 34 and 35 marked with 2 notches on E. and 4 notches on W. edges, from which,