

## Resurvey of South Bdy. of T. 3 N., R. 37 E.

Chains 58.50 60.00 60.50 80.34	<p>Stock trail, bears N.W. and S.E.</p> <p>Enter timber and dense undergrowth, bears N.W. and S.E.</p> <p>Descend gradually.</p> <p>A point about level with the <math>\frac{1}{4}</math> sec. cor. and the cor. of T. 3 N., Rs. 36 and 37 E., which is the stump of a fir, 36 ins. diam., (not a post as stated in the field notes furnished me) marked and witnessed as described by the surveyor general.</p> <p>Land, nearly level and mountainous.</p> <p>Soil, part arable, sandy loam, gravel and stone, 2nd and 3rd and 4th rates.</p> <p>Heavily timbered with pine, fir, tamarack, spruce, alder and birch, 54.69 chs.</p> <p>Densely overgrown with pine, fir, tamarack, spruce, alder, willow, birch, cascara, elder, huckleberry, thimbleberry, pine-grass, fern, rosebrier and bunch grass. 48.09 chs.</p> <p>Mountainous, heavily timbered, or lands covered with dense undergrowth, 80.34 chs.</p> <p>Good pasture land.</p> <p style="text-align: right;">August 10, 1900.</p>
	<p>Resurvey of East Boundary of T. 2 N., R. 37 E. Surveyed by Charles L. Campbell, joint contract No. 733. Dated March 22, 1901.</p>
	<p>Since T. 2 N., R. 38 E. has been subdivided I resurvey the range line between Tps. 2 N., Rs. 37 and 38 E. as follows:</p> <p>I reestablish all old obliterated cors. in their original places, destroy the markings of the old cors., which pertain to the survey W.; and establish new regular cors. common to two. secs. or quarter secs. upon the old line at lawful distances minus the northering of the S. bdy.</p> <p>July 9: At 7h 40m a.m., l.m.t., I set off 45°36' on the lat. arc.; 22°24'N. on the decl. arc., and determine a</p>