

Resurvey of East Bdy. of T. 2 N., R. 37 E.

Chains	
	Thence I run N.0° 6'W.
40.00	Set fir, 3 ft. long, 4 ins. sq., 24 ins. in the ground, for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ S. 25 on W. face, from which, A fir, 12 ins. diam., bears N.40°W., 24 lks. dist., marked $\frac{1}{4}$ S B T.
53.25	Creek, 10 lks. wide, in canyon, 500 ft. deep, course S.40°E.
53.75	Old Thomas and Ruckel Stage road, course N.W., S.E.
54.00	Leave undergrowth, bears N.W., S.E. and ascend steep S. slope.
71.00	Top of ridge, 400 ft. above creek, bears N.10°E. and S.30°E. Descend gradually along W. slope.
79.05	Intersect the old cor. of secs. 19, 24, 25 and 30, which is a fir, 18 ins. diam., marked and witnessed as described by the surveyor general. I destroy all marks which pertain to the survey E. Thence I run N.0° 02'W.
80.00	Set post, 3 ft. long, 4 ins. sq., 24 ins. in the ground, for cor. of secs. 24 and 25, marked T 2 N S 25 on S.W., and R 37 E S 24 on N.W. faces, with 4 notches on N. and 2 notches on S. edges, from which, A fir, 10 ins. diam., bears S.46°W., 104 lks. dist., marked T 2 N R 37 E S 25 B T. A pine, 36 ins. diam., bears N.46°W., 104 lks. dist., marked T 2 N R 37 E S 24 B T.
	Land, mountainous.
	Soil, loam and stony, 2nd and 3rd rate.
	Timber, pine, fir, spruce, larch, yew and tamarack.
	Undergrowth, huckleberry, mountain laurel, small firs and wild cherry.
	Mountainous land, 80.00 chs.
	July 9: At this sec. cor., I set off 22°23'N. on the decl. arc., and at 0 h 05m p.m., l.m.t., observe the sun on the meridian, the resulting lat. is 45°38',