

Resurvey of East Bdy. of T. 2 N., R. 37 E.

Chains	which is about 0'.1 greater than the proper lat.
	N.0°20'W. on old township line between secs. 19 and 24. Descend along W. slope of ridge through heavy timber and dense undergrowth.
0.48	A yellow pine, 36 ins. diam. in line. I mark with 2 notches on N. and S. edges.
32.50	Enter marshy land, bears N.W. and S.E.
33.50	Creek, 5 lks. wide, swift current, stony bottom, in canyon, 300 ft. deep, course S.30°W. Ascend E. slope.
39.25	Intersect old $\frac{1}{4}$ sec. cor., which is a post, badly decayed, marked and witnessed as described by the surveyor general. I destroy old post and set an iron-stone, 20x12x4 ins., 15 ins. in the ground, for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on E. face. I destroy all marks which pertain to the survey E.
40.00	Set ironstone, 20x10x4 ins., 15 ins. in the ground, for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on W. face, from which, A fir, 18 ins. diam., bears S.35°W., 45 lks. dist., marked $\frac{1}{4}$ S 24 B T.
	Thence I run N.0°21'W.
47.50	Leave timber and undergrowth, bears E. and W.
59.00	Enter heavy timber, bears N.30°W., S.30°E. Descend gradually.
62.25	Dry bed of stream in ravine, 150 ft. deep, course S.60°E. Ascend over rolling land.
79.03	Intersect old cor. of secs. 13, 18, 19 and 24, which is a post badly decayed, marked and witnessed as described by the surveyor general. I destroy old post and set a basalt stone, 15x12x7 ins., 10 ins. in the ground, at the same point, for cor. of secs. 18 and 19. I destroy all marks which pertain to the survey E.
	Thence I run N.0°20'E.