

Subdivisions of T. 2 N. R. 37 E. W. M.

Chains	<p>A spruce, 12 ins. diam., bears N. 12° W. 19 lks. dist., marked T 2 N R 37 E., S 30 B T.</p> <p>Land, level and mountainous.</p> <p>Soil, stony and sandy loam; 3rd and 2nd rate.</p> <p>Timber, pine, fir, spruce, tamarack and yew.</p> <p>Undergrowth, mountain laurel, willow, cherry and huckleberry.</p> <p>Mountainous or densely overgrown land,</p> <p style="text-align: right;">80.00 chs.</p>
	<p>W. on Sectional Correction Line bet. Secs. 30 and 31 Over nearly level land through heavy timber and dense undergrowth.</p>
40.00	<p>Set ironstone, 15x12x4 ins. 10 ins. in the ground, for $\frac{1}{2}$ Sec. cor. marked $\frac{1}{2}$ on N. face, from which</p> <p>A fir, 18 ins. diam., bears N. 20° E., 142 lks. dist., marked $\frac{1}{2}$ S 30 E T.</p> <p>A fir, 20 ins. diam., bears S. 31° E. 27 lks. dist., marked $\frac{1}{2}$ S 31 B T.</p>
40.25	<p>Enter scattering timber, bears N. and S Descend steep W. slope into S. Fork Umatilla River.</p>
40.60	<p>Pack Trail, course N. 10° W., S. 10° E.</p>
49.50	<p>Ravine, 50 Ft. deep, bears S. 70° W.</p>
66.75	<p>Foot of hill, 400 ft. below mountain prairie, bears N. and S.</p>
69.95	<p>S. Fork of Umatilla River, 10 lks. wide, swift current, pure water, course N. 10° W.</p> <p>Ascend E. slope of mountain.</p>
77.50	<p>More gradual ascent.</p>