

Subdivisions of T. 2 N. R. 37 E. W. M.

Chains	<p>93.00 Enter heavy fir and pine timber, bears N. and S.</p> <p>95.00 Enter scattering timber, bears N. W. and S. E.</p> <p>96.00 Top of ridge, 400 ft. above S. Fork Umatilla River. bears N. and S. Descend.</p> <p>99.00 Enter heavy pine timber, bears N. and S.</p> <p>100.54 Intersect W bdy. of T. 2 N. R. 37 E., 80 lks. S. of the cor. of Secs. 25, 30, 31 and 36 which is a post badly decayed, marked and witnessed as described, by the surveyor general. I destroy all marks on old cor. pertaining to T 2 N R 37 E., and set new post. At the exact cor. point I set fir post, 3 ft. long 4 ins sq. 24 ins. in the ground, for cor. of Secs. 25 and 36. Marked T 2 N S 36 on S W and R 36 E S 25, on N. W. Faces; with 5 notches on N. and 1 notch on S. edges. At the point of intersection. Set fir post, 3 ft. long 4 ins. sq. 24 ins. in the ground for closing cor. of Secs. 30 and 31, marked C C T 2 N R 37 E., on E. S. 31 on S., and S. 30 on N faces; with 5 grooves on N. and 1 groove on S. faces, from which A tamarack, 12 ins. diam., bears N. 51° E., 26 lks. dist., marked T 2 N R 37 E., S 30 B T. A tamarack, 10 ins. diam., bears S. 50° E., 25 lks. dist., marked T 2 N R 37 E., S 31 B T.</p> <p>Land, mountainous and level.</p> <p>Soil, stony and sandy loam; 3rd and 1st rate.</p> <p>Timber, tamarack, pine, fir and spruce.</p>
--------	--