

Subdivisions of T. 2' N R 37 E. W. M.

Chains	S. 89° 47' on random line bet. Secs. 1 and 12
40.00	Set temp. $\frac{1}{4}$ Sec. cor.
79.05	Intersect E. bdy. of Tp. 14 lks. N. of the cor., of Secs. 1 and 12, established by me. July 1901.
	N. 89° 41' W. on true line bet. Secs. 1 and 12.
	Descend along S. slope of hill through scattering timber.
13.25	Foot of ravine, 50 ft. deep, course S.
23.25	Enter dense undergrowth, and heavy timber, bears N. and S.
31.90	Spring branch 2 lks. wide, in ravine 50 ft. deep course S. 10° E.
	Ascend gradually
36.25	Leave heavy timber and dense undergrowth, bears N. and S.
39.05	Set ironstone, 20x12x4 ins. 15 ins. in the ground for $\frac{1}{4}$ Sec. cor. marked $\frac{1}{4}$ on N. face, Raise mound of stone 3 ft. base $1\frac{1}{2}$ ft. high N. of cor. Pits impracticable.
46.50	Enter dense undergrowth and heavy timber, bears N. and S.
49.00	Enter swamp, bears N. and S.
53.00	Leave swamp, bears N. W. and S. E.
56.00	Descend gradually over mountain prairie
76.00	Pack Trail, bears N. 10° W., S. 10° E.
79.05	The cor. of Secs. 1, 2, 11 and 12.
	Land, level and mountainous. Soil, stony, loam 3rd & 1st rate.
	Timber, fir, pine, spruce, yew and tamarack.
	Undergrowth, small firs, huckleberry, mountain laurel and wild cherry.
	Mountainous or heavily timbered land, 79.05 chs.
	6
	N. 0° 01' W. on random line, bet. Secs. land 2
40.00	Set Temp. $\frac{1}{4}$ Sec. cor.
73.38	Intersect N. bdy. of Tp. 5.89 chs. E. of $\frac{1}{4}$ Sec. which is a fir post, 12x3x3 ins. above ground, marked $\frac{1}{4}$ S 36 on N. face from which Tamarack 18 ins. diam., bears N. 73 $\frac{1}{2}$ ° W. 55 lks. dist., marked $\frac{1}{4}$ S 36 B T.