

Subdivisions of T. 22 N., R. 37 E., W. M.

Chains	
35.00	Leave scattering timber, bears N. W. S. E.
38.94	Set fir post, 3 ft. long, 3 ins. sq., 24 ins. in the ground for $\frac{1}{4}$ Sec. cor. marked $\frac{1}{4}$ S. 33 on W. and S. 34 on E. faces, from which A fir, 30 ins. diam., bears N. 5° E., 72 lks. dist., marked $\frac{1}{4}$ S B T. A fir, 28 ins. diam., bears S. 61° W., 26 lks. dist., marked $\frac{1}{4}$ S B T.
	This cor. stands about 200 ft. below summit of divide.
46.55	Spring branch, 3 lks. wide, course N. 70° W. Ascend gradually.
54.00	Leave dense undergrowth, bears E. and W.
59.00	Enter heavy timber, bears N. E., S. W.
69.95	Spring branch, 2 lks. wide, in ravine 50 ft. deep, course N. 40° W. Ascend.
78.94	The cor. of Secs., 27, 28, 33 and 34. Land, level and mountainous. Soil, stony and gravelly loam; 3rd and 2nd rate. Timber, fir, pine, spruce, larch, alder and tamarack. Undergrowth, mountain laurel, willow, wild cherry and huckleberry. Mountainous heavily timbered or densely overgrown lands.
70.00	chs
	N 0° 03' W. bet. Secs. 27 and 28. Pass along rolling ground facing W., through heavy timber.
3.00	Enter dense undergrowth, bears E. and W.
8.50	Dry bed of stream, 10 lks. wide, course S. 30° W.
25.61	A spruce, 24 ins. diam., on line, I mark with 2 notches on N. and S. edges.
40.00	Set basalt stone, 18x10x5 ins., 10 ins. in the ground for $\frac{1}{4}$ Sec. cor., marked $\frac{1}{4}$ on W. face, from which A fir, 36 ins. diam., bears N. 45° E., 12 lks. dist., marked $\frac{1}{4}$ S 27 B T.