

Subdivisions of T. 2 N. R. 37 E. W. M.

Chains

A fir, 28 ins. diam., bears S. 65° W., 19 lks.
 dist., marked $\frac{1}{2}$ S 28 B T.

50.00 Enter scattering timber bears E. and W.

56.75 Creek, 3 lks. wide, swift current, course N. 80° W. Ascend steep
 E. slope.

63.50 Pack trail, bears E. and W.

68.60 Top of rise, thence along mountain prairie.

80.00 Set ironstone, 20x8x6 ins., 15 ins. in the ground for
 cor. of Secs. 21, 22, 27 and 28, marked with 3 notches
 on E. and 2 notches on S. edges; from which

A fir, 24 ins. diam., bears N. 55° E., 54 lks.
 dist., marked T 2 N R 37 E., S. 24 B T.

A fir, 18 ins. diam., bears S. 87° E., 45 lks.
 dist., marked T 2 N R 37 E., S 27 B T.

A fir, 30 ins. diam., bears S 24° W., 31 lks.
 dist., marked T 2 N R 37 E., S 28 B T.

A fir, 18 ins. diam., bears N 40° W., 13 lks.
 dist., marked T 2 N R 37 E., S 21 B T.

Land, level and mountainous.

Soil, sandy loam and stony; 2nd and 3rd rate.

Timber, fir, pine, spruce and tamarack.

Undergrowth, mountain laurel, yew, huckleberry and
 wild cherry.

Mountainous, heavily timbered or densely overgrown lands.

80.00 chs.

East bet. Secs. 22 and 27. on random line.

40.00 Set Temp. $\frac{1}{2}$ Sec. cor.

79.84 Intersect N. and S. line, 14 lks. N. of the cor. of Secs.
 22, 23, 26 and 27.

Thence I run N. 89° 54' W. on true line bet. Secs. 22
 and 27.

Ascend along N. slope of mountain through heavy timber
 and dense undergrowth.