

Subdivisions of T. 2 N. R. 37 E. W. M.

Chains	<p>A pine, 8 ins. diam., bears S. 35° E., 15 lks. dist., marked $\frac{1}{2}$ S 22 B T.</p> <p>A fir, 8 ins. diam., bears N. 20° W., 10 lks. dist., marked $\frac{1}{4}$ S 15 B T.</p> <p>42.50 More gradual descent.</p> <p>43.90 Spring branch, 2 lks. wide, course S. W.</p> <p>50.00 Foot of mountain, 600 ft. below Sec. cor. Over marshy bottom not subject to inundation.</p> <p>51.00 Thomas and Fucket Fork Umatilla River, 25 lks. wide, swift current, pure water, course N. 15° E. Ascend steep E. slope of mountain.</p> <p>60.00 Leave dense undergrowth, bears N. and S.</p> <p>80.18 The cor. of Secs. 15, 16, 21 and 22. Land, mountainous. Soil, loam; 2nd rate. Timber, pine, spruce, alder, fir and tamarack. Undergrowth, mountain laurel, huckleberry and small firs. Mountainous land. 80.18 chs.</p>
	<p>N. 0° 03' W. on true line bet. Secs. 15 and 16. Descend along E. slope of mountain, through heavy timber.</p> <p>13.50 Deep ravine, 150 ft. deep, course N. 70° E. Spring just above line.</p> <p>15.00 Enter scattering timber, bears E. and W. Ascend.</p> <p>23.00 Top of ridge, 300 ft. high, bears E. and W. Abrupt descent.</p> <p>31.25 Foot of ravine, 150 ft. deep, course E. Enter heavy timber, bears N. 60° E., S. 60° W.</p> <p>40.00 Set fir post, 3 ft long, 3 ins. sq., 24 ins. in the ground for $\frac{1}{4}$ Sec. cor., marked $\frac{1}{4}$ S. 16 on W. and S. 15 on E faces, from which A fir, 18 ins. diam., bears E. 39 lks. dist., marked $\frac{1}{4}$ S B T.</p>