

Subdivisions of T. 2 N. R 37 E. W. M.

Chains	Undergrowth, small firs, huckleberry and mountain laurel. Mountainous land, 80.00 chs. July 31:
	E. on random line bet. Secs. 21 and 28.
40.00	Set temp. $\frac{1}{4}$ Sec. cor.
79.88	Intersect N. and S. line 21 lks. N. of the cor. of Secs. 21, 22, 27 and 28. Thence I run N. 89° 51' W. on true line bet. Secs. 21 and 28. Over nearly level land on summit of mountain, through heavy timber.
7.36	A fir, 18 ins. diam., on line I mark with 2 notches on E. and W. edges.
24.00	Enter scattering timber, bears N. and S.
25.75	Dry bed of stream, 5 lks. wide, course N. 10° W. Ascend gradually.
34.75	Enter sheep corral bears N. and S.
38.25	Leave sheep corral bears N. and S.
39.94	Set fir post, 3 ft. long, 3 ins. sq. 24 ins. in the ground, for $\frac{1}{4}$ Sec. cor. marked $\frac{1}{4}$ S. 21 on N and S. 28 on S. faces, from which A fir, 10 ins. diam., bears N. 70° E., 71 lks. dist., marked $\frac{1}{4}$ S B T. A fir, 14 ins. diam., bears S. 44° W 10 lks. dist., marked $\frac{1}{4}$ S B T.
42.80	Summit of ridge, 100 ft. above Sec. cor., bears N. 20° W., S. 20° E.
43.25	Pack trail, bears N. 20° W., S. 20° E. Descend steep W. slope of mountain.
77.50	Foot of mountain, 800 ft. below top of ridge. Over bottom land, not subject to inundation.
79.00	Creek, 15 lks. wide, swift current, stony bottom, pure water, course N. 10° W. Ascend steep E. slope through heavy timber, bears N. and S.