

Subdivisions of T. 2 N. R. 37 E. W. M.

| | |
|--|--|
| Chains | <p>Land level and mountainous. Soil, stony and rich loam; 3rd and 1st rate. Timber, pine, fir and tamarack. Undergrowth, laurel, huckleberry and small firs. Mountainous or heavily timbered land, 80.00 chs.</p> |
| <p>40.00 79.90 3.75 39.95 46.50 47.00 65.75 79.90</p> | <p>S. 89° 45' E. on random line bet. Secs. 9 and 16. Set temp. $\frac{1}{4}$ Sec. cor. Intersect N. and S. line 35 lks. S. of the cor. of Secs. 9, 10, 15 and 16. Thence I run W. on true line bet. Secs. 9 and 10. Ascend E. slope of mountain through heavy timber. Top of ridge point, 100 ft. above Sec. cor. bears N. and S. Thence along N. slope of ridge, through heavy timber and dense thickets. Set fir post, 3 ft. long, 3 ins. sq., 24 ins. in the ground, for $\frac{1}{4}$ Sec. cor., marked $\frac{1}{4}$ S. 9 on N. and S. 16 on S. faces, from which A fir, 10 ins. diam., bears N. 50° E., 18 lks. dist., marked $\frac{1}{4}$ S B T. A fir, 12 ins. diam., bears S. 55° E., 16 lks. dist., marked $\frac{1}{4}$ S B T. Leave dense thicket and enter scattering timber, bears N. and S. Enter East edge of plateau on Chimney Horn Ridge, bears N. and S. Enter heavy timber bears N. and S. Thence of Secs. 8, 9, 16 and 17. Land level and mountainous. Soil, rich loam and stony; 1st and 3rd rate. Timber, pine and fir. Mountainous or heavily timbered land, 60.65 chs.</p> |