

Subdivisions of T. 2 N. R. 37 E. W. M.

Chains	
	N. 0° 04' W. on true line bet. Secs. 8 and 9. Over nearly level land on Chimney Horn Ridge, through heavy timber.
8.00	Enter scattering timber, bears E. and W.
8.75	Pack Trail, bears N. E., S. W.
9.00	Leave plateau and descend along W. slope of divide.
21.00	Ascend gradually.
35.00	Chimney Horn Ridge, bears N. W., S. E. Descend along steep E. slope of ridge, mountain bears N. 20° W., S. 20° E.
35.10	Pack trail, bears N. W., S. E.
35.50	Enter heavy timber, and dense undergrowth, bears N. W. and S. E.
40.00	Set fir post, 3 ft. long 3 ins. sq., 24 ins in the ground for $\frac{1}{4}$ Sec. cor., marked $\frac{1}{4}$ S. 8 on W. and S. 9 on E. faces, from which A fir, 16 ins. diam., bears N. 60° E., 12 lks. dist., marked $\frac{1}{4}$ S B T. A fir, 12 ins. diam., bears N. 28° W., 24 lks. dist., marked $\frac{1}{4}$ S B T. This cor. stands about 300 ft. below top of Chimney Horn Ridge.
61.90	Spring branch, 2 lks. wide, course N. 70° E.
63.00	Enter scattering timber, bears E. and W.
80.00	Set ironstone, 24x14x12 ins., 18 ins. in the ground for cor. of Secs. 4, 5, 8 and 9, marked with 4 notches on E. and 5 notches on S. edges, from which A fir, 10 ins. diam., bears S. 24° E., 69 lks. dist., marked T 2 N R 37 E., B T. A fir, 12 ins. diam., bears S. 48° W., 80 lks. dist., marked T 2 N R 37., S B B T. No other trees in limits. Raise mound of stone, 3 ft. base, 2 ft. high W. of cor.. Pits impracticable.

S 9