

Subdivisions of T. 2 N. R 37 E. W. M.

Chains 39.10	<p>Set ironstone, 24x15x8 ins., in mound of stone, for $\frac{1}{4}$ Sec. cor. marked $\frac{1}{4}$ on W. face, from which</p> <p>A pine, 30 ins. diam., bears N. 70° E., 253 lks. dist., marked $\frac{1}{4}$ S 32 B T.</p> <p>A fir, 40 ins. diam., bears N. 10° W., 298 lks. dist., marked $\frac{1}{4}$ S 31 B T.</p>
42.25	Leave prairie and enter scattering timber, bears E. and W.
42.91	A yellow pine, 36 ins. diam., on line, I mark with 2 notches on N. and S sides.
61.25	Leave timber and enter prairie, bears E. and W.
69.75	Enter heavy timber, and undergrowth bears E. and W
71.90	Foot of ravine, 100 ft. deep, course W.
74.10	Pack trail, bears E. and W.
79.10	The cor. of Secs. 29, 30, 31 and 32.
	Land, rolling.
	Soil, stony and gravelly loam; 3rd and 2nd rate.
	Timber, pine, fir, spruce and tamarack.
	Undergrowth, huckleberry, mountain laurel and small firs.
	Heavily timbered land, 47.00 chs.
	N. 0° 05' W. bet. Secs. 29 and 30.
	Over nearly level ground, through heavy timber and dense undergrowth.
20.00	Descend gradually.
38.00	Dry bed of stream, 5 lks. wide, course N. 60° E. Water comes to surface 4.00 chs. below line.
	Ascend gradually.
40.00	A fir, 30 ins. diam., for $\frac{1}{4}$ Sec. cor., I mark $\frac{1}{4}$ S 30 on W. and S. 29 on E. faces, from which
	A fir, 10 ins. diam., bears S. 64° E., 30 lks. dist., marked $\frac{1}{4}$ S B T.
	A fir, 18 ins. diam., bears S. 78° W., 65 lks. dist., marked $\frac{1}{4}$ S B T.
42.50	Leave timber and enter rocky prairie, bears E. and W.
45.00	Top of ridge, 300 ft. high, bears N. 80° E., S. 80° W.