

Subdivisions of T. 2 N. R. 37 E. W. M.

Chains	
	<p>A fir, 16 ins. diam., bears N. 85° W., 110 lks. dist., marked T 2 N R 37 E., S 7 B T.</p> <p>This Sec. cor. stands about 200 ft. below the <math>\frac{1}{4}</math> Sec. cor. Land, mountainous.</p> <p>Soil, stony 3rd rate.</p> <p>Timber, pine, fir, spruce, larch, yew and tamarack.</p> <p>Undergrowth, small firs, wild pherry, huckleberry and mountain laurel.</p> <p>Mountainous land, 80.00 chs.</p>
40.00	<p>S. 89° 54' E. on random line bet. Secs. 8 and 17.</p> <p>Set. temp. <math>\frac{1}{4}</math> Sec. cor.</p>
79.90	<p>Intersect N. and S. line, 35 lks. S. of the cor. of Secs. 8, 9, 16 and 17.</p>
	<p>Thence I run S 89° 51' W. on true line bet. Secs. 8 and 17.</p>
	<p>Descend gradually through heavy timber.</p>
2.30	<p>Trail to Bingham Springs, bears N. and S.</p>
3.00	<p>Leave Chimney Horn Ridge and descend steep W. slope of mountain.</p>
5.00	<p>Enter very scattering timber, bears N. and S.</p>
39.95	<p>The point for <math>\frac{1}{4}</math> Sec. cor. falls on a ledge, 36x30x5 ins. above ground. I cut a cross at the exact cor. point for <math>\frac{1}{4}</math> Sec. cor. and mark <math>\frac{1}{4}</math> on N. side of cross. No trees in limits. I mark B. O. on a boulder, 4x3x2 ft. bears N. 70° E., 2 lks. dist. A. B. O. on ledge 3x1x1 ft. bears S. 30° E., 7 lks. dist., There is no suitable place for mound of stone, Pits impracticable.</p>
	<p>This cor. stands about 300 ft. below Chimney Horn Ridge</p>
46.50	<p>Foot of mountain 400 ft. below ridge Creek, 15 lks. wide, swift current, stony bottom, course N. 10° E.</p>
	<p>Ascend steep precipitous E. slope of mountain, bears</p>
	<p>N. and S.</p>
73.95	<p>Ravine, 150 ft. deep course N. 60° E.</p>
79.90	<p>Large spring just below line.</p>
<del>79.90</del>	<p><del>The cor. of Secs. 7, 8, 17 and 18</del></p>