

South Bdy. T.2 S.,R.30 E.,W.M.
 As surveyed by George Williams & George S. Pershin,
 U.S. Deputy Surveyors
 Under Contract No. 154
 Dated June 6th, 1871.

Chains		Feet
	From the Cor. to Tps. 2 & 3 S.,Rs.,29 & 30 E.	
	I run	
	E. on true line along S. Bdy. of Sec. 31	
	Var. 20°35'E.	
21.00	A canyon, brs. N.E.	-80
37.75	Set stone, 20 x 8 x 7 on N.W. hillside for $\frac{1}{4}$ Sec. Cor.	+150
	Var. 21°16'E.	
70.00	A spring branch runs N.	-160
77.75	Set stone, 30 x 10 x 4 on W. hillside for Cor. to Secs. 31,	+50
	32, 5 & 6.	
	Land; rolling hills.	
	2nd and 3rd rate.	
	E. on true line along S. Bdy. of Sec. 32	
	Var. 21°28'E.	
14.00	Top of ridge, brs. N. & S.	+120
30.50	A ravine, brs. N.E.	-150
40.00	Set stone, 18 x 6 x 4 on N.W. hillside for $\frac{1}{4}$ Sec. Cor.	
	Var. 21°14'E.	
42.00	Top of hill.	+ 8
53.75	A road from the settlements below the timber in Blue Mts.	+130
	brs. N.W. & S.E.	
80.00	Set stone, 18 x 6 x 4 on W. side, near top of ridge for Cor.	+150
	to Secs. 4, 5, 32 & 33.	
	Land; high, broken ridges, 2nd rate.	
	E. on true line along the S. Bdy. of Secs. 33.	
	Var. 20°42'E.	
4.00	Top of ridge, brs. N. & S.	+ 10
35.00	A spring branch runs N.	-150
40.00	Set stone, 20 x 10 x 4 on N. hillside for $\frac{1}{4}$ Sec. Cor.	+ 50
	Var. 20°12'E.	
57.75	A canyon, brs. N.W.	- 50
80.00	Set a stone, 22 x 8 x 6 on S.W. hillside for Cor. to Secs.	+35
	3, 4, 33 & 34.	
	Land; hilly and broken, 2nd & 3rd rate.	