

S. Bdy., T. 2 S., R. 30 E., W.M.

Chains		Feet
	E. on true line along S. Bdy. of Sec. 34. Var. 21°03'E.	
6.00	Top of hill.	+ 50
18.00	A ravine, brs. N.	-120
39.50	A brook, 5 lks. wide, runs N.	-300
40.00	Set stone, 22 x 10 x 5 on E. bank of brook, for $\frac{1}{4}$ Sec. Cor. Var. 19°42'E.	
80.00	Set stone, 24 x 6 x 5 on top of hill for Cor. to Secs. 32, 33, 34 & 35. Land; high, steep, broken hills. 2nd & 3rd rate, part worthless.	
	E. on true line along S. Bdy. of Sec. 35. Var. 21°50'E.	
32.50	A ravine brs. N.	-450
40.00	Set stone, 18 x 10 x 8 on W. hillside for $\frac{1}{4}$ Sec. Cor. Var. 21°55'E.	
48.00	Top of hill	+150
69.25	Butter Creek, 20 lks. wide, runs N.W.	-450
80.00	Set stone, 18 x 8 x 7 on S. point of spur for Cor. to Secs. 1, 2, 35 & 36. Land; high, broken bluffs. 3rd rate, large part worthless.	
	E. on true line along S. Bdy. of Sec. 36 Var. 20°42'E.	
3.00	A ravine, brs. S.W.	- 10
35.00	Top of bluff, a table land	+350
40.00	Set stone, 22 x 10 x 6 for $\frac{1}{4}$ Sec. Cor. Var. 20°12'E.	
80.00	To a point for Cor. to Tps. 2 & 3 S., Rs. 30 & 31 E. Set stone, 20 x 8 x 7 and raised mound of stone as per instructions. Land; western part, broken eastern part, level. 2nd & 3rd rate. Oct. 20, 1871.	