

East Bdy. , T. 2 S., R.30 E.,W.M.  
As surveyed by same Surveyors under same Contract & Date.

Chains		Feet
	From the Cor. to Tps. 2 & 3, Rs. 30 & 31 E., I run N. along the E. Bdy. of Sec. 36  Var. 20°55' E.	
35.00	A road from settlements to timber, brs. N.W. & S.E.	- 80
37.00	A canyon, brs. N.W.	- 10
40.00	Set stone, 18 x 8 x 4 on W. hillside for $\frac{1}{4}$ Sec. Cor.,  Var. 18°45' E.	
80.00	Set stone, 24 x 8 x 6 on W. hillside for Cor. to Secs. 25 and 36, 30 & 31.  Land; rolling, 2nd & 3rd rate.	
	N. on E. Bdy. of Sec. 25.  Var. 22°51' E.	
37.00	A road, brs. N.E. & S.W.	-160
40.00	Set stone, 22 x 12 x 3 on S.E. hillside for $\frac{1}{4}$ Sec. Cor.  Var. 19°18' E.	+ 20
80.00	Set stone, 20 x 7 x 5 on E. hillside for Cor. to Sec, 24, 25, 19 & 30.  Land; hilly and somewhat broken, 2nd & 3rd rate.	+ 60
	N. on E. Bdy. of Sec. 24.  Var. 20°04' E.	
40.00	Set stone, 16 x 8 x 6 on E. Side near top of hill for $\frac{1}{4}$ Sec. Cor.  Var. 19°48' E.	+ 60
74.50	A road brs. N.W. & S.E. Canyon brs. N.W.	-200
80.00	Set stone, 22 x 7 x 5 on S.W. hillside for Cor. to Secs. 13, 24, 18 & 19.  Land; hilly and broken, 2nd & 3rd rate.	+ 60
	N. on E. Bdy. of Sec. 13.  Var. 21°20' E.	
25.00	Top of hill	+160
40.00	Set stone, 16 x 8 x 6 for $\frac{1}{4}$ Sec. Cor.  Var. 21°46' E.	- 10
	Gradually descending.	