

E. Bdy. T.2 S.,R.30 E.,W.M.

Chains		Feet
80.00	Set stone, 24 x 8 x 3 for Cor. to Secs. 12, 13, 7 & 18. Land; S. part broken-N.55 chs. a plain, inclined to the N. Land 2nd & 3rd rate.	
	N. on E. Bdy. Sec. 12. Var. 21°02'E.	
40.00	Set stone, 18 x 9 x 4 for $\frac{1}{4}$ Sec. Cor. Var. 21°28'E.	80
53.00	A canyon, brs. W.	30
75.00	A table land	120
80.00	Set stone, 18 x 8 x 5 for Cor. to Secs. 1, 12, 7 & 8. Land; rolling hills. 2nd & 3rd rate.	
	N. on E. Bdy. of Sec.1. Var. 22°10'E.	
40.00	Set stone, 18 x 9 x 4 for $\frac{1}{4}$ Sec. Cor. Var. 21°43'E.	
80.00	Set stone, 26 x 8 x 7 for Cor. to Tps. 1 & 2 S.,Rs. 30 & 31 E., raised mound of stone as per instructions. Land; a plain, slightly inclined N., excellent 2nd rate. Oct. 21, 1871	
	W. Bdy. T.2 S.,R.30 E.,W.M. As surveyed by same surveyors. Under same Contract & Date.	
	From the Cor. to Tps. 2 & 3 S.,Rs. 29 & 30 E., I run N. along the E. Bdy. of Sec. 36 Var. 20°35'E.	
3.50	A ravine brs. E.	10
25.00	Top of hill	220
40.00	Set stone, 18 x 8 x 4 on E. hillside for $\frac{1}{4}$ Sec. Cor. Var. 21°00'E.	30
59.25	A ravine, brs. N.E.	150
76.00	A ravine, brs. S.E.	40
80.00	Set stone, 18 x 8 x 6 on S.W. hillside for Cor. to Secs. 25, 36, 30, & 31. Land; high rolling, 2nd & 3rd rate.	60