

W. Bdy. T.2 S., R.30 E., W.M.

| Chains |   | Feet  |
|--------|---|-------|
|        | N. on E. Bdy. Sec. 25.  |       |
|        | Var. 21°35'E.   |       |
| 4.00   | Top of hill   | + 15  |
| 16.00  | A wide ravine hrs. N.E.   | - 80  |
| 24.00  | Top of hill   | + 80  |
| 40.00  | Set stone, 20 x 14 x 5 on N. hillside for $\frac{1}{4}$ Sec. Cor.         | - 50  |
|        | Var. 21°50'E.   |       |
| 80.00  | Set stone, 20 x 8 x 5 at foot of hill for Cor. to Secs. 24, 25, 19 & 30.  | + 450 |
|        | Land; high, broken bluffs. 2nd & 3rd rate, part worthless.                |       |
|        | N. on E. Bdy. of Sec. 24.   |       |
|        | Var. 20°15'E.   |       |
| 3.75   | Johnson Creek, 25 lks. wide, runs N.E.                                    | - 25  |
| 7.25   | Foot of hill, hrs. N.E. & S.W.  |       |
| 25.00  | On spur, hrs. S.E.  | + 280 |
| 40.00  | Set stone, 24 x 12 x 3 on E. hillside for $\frac{1}{4}$ Sec. Cor.         |       |
|        | Var. 20°30'E.   |       |
| 46.25  | A ravine, hrs. S.E.   | - 20  |
| 80.00  | Set stone, 24 x 8 x 5 on S.W. hillside for Cor. to Secs. 13, 24, 18 & 19. | + 250 |
|        | Land; high broken bluffs, 2nd & 3rd rate, large part worthless.           |       |
|        | N. on E. Bdy. of Sec. 13.   |       |
|        | Var. 21°46'E.   |       |
| 4.00   | Top of hill. A gradual descent.   | + 15  |
| 40.00  | Set stone, 18 x 7 x 6 for $\frac{1}{4}$ Sec. Cor.                         | - 40  |
|        | Var. 20°35'E.   |       |
| 65.50  | A ravine hrs. N.E.  | - 90  |
| 80.00  | Set stone, 22 x 12 x 4 on S.E. hillside for Cor. to Secs. 12, 13, 7 & 18. |       |
|        | Land; high, somewhat broken, 2nd rate.                                    |       |
|        | N. on E. Bdy. Sec. 12   |       |
|        | Gradual descent. Var. 19°40'E.  |       |