

W. Bdy., T. 2 S., R. 30 E., W.M.

Chains		Feet
40.00	Set stone, 28 x 10 x 5 for $\frac{1}{4}$ Sec. Cor. Var. 19°25'E.	40
45.75	A ravine brs. N.E.	20
80.00	Set stone, 26 x 8 x 6 for Cor. to Secs. 1, 12, 6 & 7. Land; high, somewhat broken, slopes N. 2nd rate.	20
N. on E. Bdy. Sec. 1. Var. 22°06' E.		
40.00	Set stone, 20 x 10 x 8 on N. W. hillside for $\frac{1}{4}$ Sec. Cor. Var. 21°38'E.	280
77.50	County road from Butter Creek to little Butter Creek, brs. N.E. & S.W.	
80.00	Set stone, 24 x 10 x 8 in middle of canyon for Cor. to Tps. 1 & 2, Rs. 29 & 30 E., raised mound of stone, as per instructions. Canyon brs. N.E. Land; hilly, 2nd rate. Sept. 7th, 1871.	60
Subdivisional Lines, T.2 S., R.30 E., W.M. As surveyed by George S. Pershin, U.S. Deputy Surveyor, Under Contract No. 293 Dated Aug. 12, 1878.		
From the Cor. to Secs. 35 & 36 on S. Bdy. of Tp. I run N. bet. Secs. 35 & 36. Up along S.W. hillside. Var. 20°42'E.		
30.00	On bench or table land	250
38.50	To head of ravine, course W.	
40.00	Set stone, 14 x 10 x 4 on N. hillside for $\frac{1}{4}$ Sec. Cor.	20
46.00	Bottom of ravine	50
53.00	On table land	70
66.00	Road, S.E. & N.W.	
80.00	Set stone, 14 x 10 x 10 for Cor. to Secs. 25, 26, 35 & 36. Dug pits and drove pine stake as per instructions. Land; surface S. part broken, N. 14 chs. level; Soil; 2nd rate on hillside, on table land extra 2nd rate. Good bunch grass.	