

Subdivisional Lines, T.2 S., R.30 E., W.M.

Chains		Feet
5.00	On table land	+ 20
25.00	Begin to descend.	
36.00	Ravine opens to N.	-80
39.95	Set stone, 14 x 8 x 6 for $\frac{1}{4}$ Sec. Cor.	+50
45.00	On table land	+30
79.90	The Cor. to Secs. 23, 24, 25 & 26. Land; surface partly level. Soil; on benches, extra 2nd rate. hillsides 2nd & 3rd rate. Good grass. Sec. 25 is nearly all good wheat land and mostly level.	-30
N. bet. Secs. 23 & 24. Var. 21°45'E.		
40.00	Set stone, 18 x 10 x 8 on level for $\frac{1}{4}$ Sec. Cor.	+ 30
80.00	Set stone, 18 x 12 x 5 on level for Cor. to Secs. 13, 14, 23 & 24. Dug pits and drove pine stake as per instructions. Land; surface along this mile is undulating; Soil; mostly excellent 2nd rate and good for wheat. Good bunch grass.	
E. on random line bet. Secs. 13 & 24. Var. 21°E.		
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.10	Intersected E. Bdy., 44 lks. S. of stone Cor. to Secs. 13 & 24, from which Cor. I run S.89°41'W. on true line bet. Secs. 13 & 24. Var. 21°20'E.	
5.00	Foot of hill, S.E. & N.W.	-40
25.00	Across bottom	
40.00	Set stone, 18 x 14 x 5 on E. hillside for $\frac{1}{4}$ Sec. Cor.	+100
80.10	The Cor. to Secs. 13, 14, 23 & 24 Land; surface partly broken. Soil; greater part extra 2nd rate, some 3rd rate. Good for grain, good bunch grass. About $\frac{1}{2}$ of Sec. 24 is level table land.	+ 40
Sept. 2, 1878.		