

Subdivisional Lines, T.2 S., R.30 E., W.M.

Chains		Feet
	N. bet. Secs. 13 & 14. Gradual descending. Var. 21°E.	
36.00	Steep descent	80
40.00	Set stone, 15 x 8 x 5 on N. hillside for 1/4 Sec. Cor.	50
44.00	Foot of hill, small valley, N.W. & S.E.	50
52.00	Begin to ascend	
76.00	Top of hill	200
80.00	Set stone, 17 x 10 x 6 for Cor. to Secs. 11, 12, 13 & 14. Dug pits and drove pine stake as per instructions. Land; surface, broken. Soil; part 2nd and 3rd rate and stony. Good grass.	
<hr/>		
	E. on random line bet. Secs. 12 & 13. Var. 19°E.	
40.00	Set temp. 1/4 Sec. Cor.	
80.04	Intersected E. Bdy., 70 lks. S. of stone Cor. to Secs. 12 and 13, from which Cor. I run S.89°30'W. on true line bet. Secs. 12 & 13. Var. 21°20'E.	
40.02	Set stone, 20 x 10 x 6 for 1/4 Sec. Cor.	30
80.04	The Cor. to Secs. 11, 12, 13 & 14. Land; surface nearly level. Soil; along line good 2nd rate, excellent grass. About 200 Acres in N.E. Cor. is nearly level and good wheat land. Remainder 2nd & 3rd rate.	30
<hr/>		
	N. bet. Secs. 11 & 12 Var. 19°E.	
40.00	Set stone, 18 x 12 x 6 for 1/4 Sec. Cor.	70
41.00	Road, N.E. & S.W.	
64.50	Sheep corral	80
71.50	Cabin and spring, 150 lks. W. of line	
80.00	Set stone, 16 x 10 x 8 on S.W. rocky hillside for Cor. to Secs. 1, 2, 11 & 12. Cannot dig pits. I build mound of stone around stake in lieu of pits. Land; surface gradually descends to canyon, then up to Cor. Soil; part 2nd & part 3rd rate. Good bunch grass.	75