

Subdivisional Lines, T.2 S., R.30 E., W.M.

Chains		Feet
	E. on random bet. Secs. 1 & 12. Var. 21°45'E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.40	Intersected E. Bdy., 10 lks. S. of Cor. to Secs. 1 & 12, from which Cor. I run S.89°56'W. on true line bet. Secs. 1 & 12. Var. 22°10'E.	
40.20	Set stone, 20 x 6 x 5 for $\frac{1}{4}$ Sec. Cor.	-20
80.40	The Cor. to Secs. 1, 2, 11 & 12 Land; surface sloping W. Soil; E.60 chs., good 2nd rate; W.20 chs., 3rd rate. Most of Sec. 12 is good 2nd rate soil and good for farming.	-120
	N. on a random line bet. Secs. 1 & 2. Var. 21°45'E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.22	Intersected N. Bdy., 40 lks. E. of stone Cor. to Secs. 1 & 2; from which Cor. I run S.17'E. on true line bet. Secs. 1 & 2. Var. 20°18'E.	
21.00	Ravine opens W.	-100
40.22	Set stone, 20 x 8 x 6 on N. hillside for $\frac{1}{4}$ Sec. Cor.	† 75
46.00	Ravine opens W.	- 60
80.22	The Cor. to Secs. 1, 2, 11 & 12. Land; surface much broken. Soil; 2nd rate and stony. Good grass. E. $\frac{1}{2}$ of Sec. 1, nearly level. W. $\frac{1}{2}$ much broken and stony. Sept. 3, 1878.	† 50
	N. bet. Secs. 34 & 35. Down steep irregular descent. Var. 21°50'E.	
35.50	Creek, course N.W.	-300
40.00	Set stone, 18 x 10 x 6 for $\frac{1}{4}$ Sec. Cor.	† 20
76.00	Top of bluff.	†300
80.00	Set stone; 16 x 10 x 5 on level for Cor. to Secs. 26, 27, 34 & 35. Dug pits and drove pine stake as per instructions.	