

Subdivisional Lines, T.2 S., R.30 E., W.M.

Chains	Feet
	Land; surface, steep hillside. Soil; 3rd rate and stony, very little bottom land on creek. Good grass, willow and alder brush on creek.
	E. on random line bet. Secs. 26 & 35. Var. 21°15'E.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.42	Intersected N. & S. line, 34 lks. N. of Cor. to Secs. 25 & 26, 35 & 36, from which Cor., I run N.89°45'W. on true line bet. Secs. 26 & 35. Var. 19°45'E.
31.50	Road, N.W. & S.E.
40.21	Set stone, 20 x 14 x 4 on level for $\frac{1}{4}$ Sec. Cor.
80.42	The Cor. to Secs. 26, 27, 34 & 35. Land; surface level. Soil; extra 2nd rate, good grass. Sec. 35 has about 150 acres of excellent level land on N.W. side. Remainder, 2nd & 3rd rate, very broken and South hillside very stony
	N. bet. Secs. 26 & 27. Var. 21°45'E.
11.50	Road, E. & W.
23.00	" N.W. & S.E.
40.00	Set stone, 18 x 10 x 6 on level for $\frac{1}{4}$ Sec. Cor. Descending E. hillside.
80.00	Set stone, 14 x 8 x 7 on E. hillside for Cor. to Secs. 22, 23, 26 & 27. Dug pits and drove pine stake as per instructions. Land; surface undulating. Soil; good 2nd rate. Good bunch grass.
	E. on random line bet. Secs. 23 & 26. Var. 18°30'E.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.10	Intersected N. & S. line, 44 lks. N. of Cor. to Secs. 23,