

Subdivisional Lines, T.2 S., R.30 E., W.M.

Chains		Feet
	24, 25 & 26, from which Cor. I run N.89°41'W. on true line bet. Secs. 23 & 26. Var.21°45'E.	
9.00	Shallow ravine, N.	- 50
40.05	Set stone, 14 x 12 x 5 on ridge for $\frac{1}{4}$ Sec. Cor.	+ 60
61.00	Ravine opens N.	-100
80.10	The Cor. to Secs. 22, 23, 25 & 27. Land; surface hilly. Soil; part 2nd rate, part 3rd rate, good grass. The S. $\frac{1}{2}$ of Sec. 26 is extra 2nd rate soil and well adapted to cul- tivation.	+ 50
	N. bet. Secs. 22 & 23. Var.18°30'E.	
40.00	Set stone, 14 x 8 x 6 on E. hillside for $\frac{1}{4}$ Sec. Cor.	
70.00	Begin descending rocky point.	
80.00	Set stone, 14 x 12 x 8 on rocky point for Cor. to Secs. 14, 15, 22 & 23. Cannot dig pits. I raise mound of stone around pine stake. Land; surface broken. Soil; 2nd rate. Good grass. Not adapted to farming.	- 50
	E. on random line bet. Secs. 14 & 23. Var. 21°E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.22	Intersected N. & S. line, 12 lks. N. of Cor. to Secs. 13, 14, 23 & 24, from which Cor. I run N.89°55'W. on true line bet. Secs. 14 & 23, Var. 21°E.	
40.11	Set stone, 14 x 8 x 6 for $\frac{1}{4}$ Sec. Cor.	- 40
61.40	Spring branch, course N.	-140
80.22	The Cor. to Secs. 14, 15, 22 & 23 Land; surface broken. Soil; 2nd & 3rd rate. Good grass. Sec. 23 is considerably broken. Soil on N. hillside good 2nd rate. S. hillside, 3rd rate & stony. Good for grazing.	+130