

Subdivisional Lines, T.2 S., R.30 E., W.M.

Chains		Feet
	N. bet. Secs. 14 & 15.	
	Var. 21° E.	
31.00	Foot of hill and cross ravine, opens N.E.	-14
40.00	Set stone, 18 x 12 x 10 on W. side of ravine for $\frac{1}{4}$ Sec. Cor.	-D
79:00	Bed of creek, small amount of running water, course N.W.	-50
80.00	Set stone, 18 x 12 x 10 on N.E. side of creek for Cor. to Secs. 10, 11, 14 & 15. Dug pits and drove stake as per instructions.	
	Land; surface hilly.	
	Soil; 2nd rate. Good grass.	
E. on random line bet. Secs. 11 & 14.		
	Var. 21° 30' E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.96	Intersected N. & S. line, 4 lks. S. of Cor. to Secs. 11, 12, 13 & 14, from which Cor. I run S. 89° 58' W. on true line bet. Secs. 11 & 14.	
	Var. 19° E.	
19.00	Begin descent of S.W. hillside.	
39.98	Set stone, 20 x 14 x 10 on S.W. hillside for $\frac{1}{4}$ Sec. Cor.	-40
78.50	Road, N.W. & S.E.	-250
79.96	The Cor. to Secs. 10, 11, 14 & 15. ✓	
	Land; surface, W. 60 chs. very broken.	
	Soil; 3rd rate and stony, good grass.	
	Sec. 14 is very broken, contains a tract of about 20' A. of good bottom land, near center of Sec. Remainder 2nd & 3rd rate. John Car's house is near center of Sec.	
N. bet. Secs. 10 & 11.		
	Var. 21° 30' E.	
40.00	Set stone, 14 x 12 x 6 on S. side of ravine for $\frac{1}{4}$ Sec. Cor.	+ 30
41.00	Ravine opens W. along S.W. hillside	-15
80.00	Set stone, 17 x 12 x 5 for Cor. to Secs. 2, 3, 10 & 11.	
	Dug pits and drove pine stake as per instructions.	
	Land; surface along this mile very broken. Soil; poor 3rd rate and very stony. Good grass. Sept. 4, 1878.	