

Subdivisional Lines, T.2 S.; R.30 E., W.M.

| Chains | | Feet |
|--------|--|------|
| | E. on a random line bet. Secs. 2 & 11. Var. 21°E. | |
| 40.00 | Set temp. $\frac{1}{4}$ Sec. Cor. | |
| 80.40 | Intersected N. & S. line, 12 lks. S. of Cor. to Secs. 1, 2, 11 & 12, from which Cor. I run S.89°55'W. on true line bet. Secs. 2 & 11. Var. 21°45'E. | |
| 9.50 | Spring branch, N.W. | -80 |
| 40.20 | Set stone, 20 x 10 x 7 for $\frac{1}{4}$ Sec. Cor. | +150 |
| 47.00 | On table land | +40 |
| 74.00 | Begin descent. | |
| 80.40 | The Cor. to Secs. 2, 3, 10 & 11. Land; surface broken. Soil; 2nd & 3rd rate. Good grass. S.W. $\frac{1}{2}$ of Sec. 11 is very broken and stony. N.E. $\frac{1}{2}$, rolling & good 2nd rate soil and good for farming. | -60 |
| | N. on random line bet. Secs. 2 & 3. Var. 21°E. | |
| 40.00 | Set temp $\frac{1}{4}$ Sec. Cor. | |
| 80.60 | Intersected N. Bdy. , 86 lks. E. of stone Cor. to Secs. 2 & 3, from which Cor. I run S.37' E. on true line bet. Secs. 2 & 3. Var. 26°26'E. | |
| 40.60 | Set stone, 16 x 8 x 6 for $\frac{1}{4}$ Sec. Cor. | +60 |
| 74.00 | Begin descent | +30 |
| 80.60 | The Cor. to Secs. 2, 3, 10 & 11 Land; surface broken. Soil; part 2nd and part 3rd rate. Good grass. Sec. 2 is considerably broken. Some 2nd rate soil, greater part 3rd rate. Good grass. Adapted to grazing. | -50 |
| | N. bet. Secs. 33 & 34. Var. 21°03'E. | |
| 40.00 | Set stone, 14 x 12 x 8 on N. hillside for $\frac{1}{4}$ Sec. Cor. | -60 |
| 60.00 | Jesse Hardesty's house brs. N.87°E. | |