

Subdivisional Lines, T. 2 S., R. 30 E., W.M.

Chains		Feet
65.00	Fence and road, N.W. & S.E.	-300
72.00	House bears S.66°E.	
74.00	Creek, 25 lks. wide, course N.W.	
80.00	Set stone, 20 x 10 x 8 on rocky point for Cor. to Secs. 27, 28, 33 & 34. I raise mound of stone around stake in lieu of pits which cannot be dug.	
	Land; surface steep hillside, except narrow creek bottom. Good grass. Alder, willow and cottonwood along creek.	
	E. on random line between Secs. 27 & 34. Var. 20°30'E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.66	Intersected N. & S. line, 10 lks. S. of Cor. to Secs. 26, 27, 34 & 35, from which Cor. I run S. 89° 56' W. on a true line bet. Secs. 27 & 34. Var. 21°15'E.	
17.00	Begin to descend S.W. hillside	
40.33	Set stone, 24 x 10 x 8 for $\frac{1}{4}$ Sec. Cor.	- 60
80.66	The Cor. to Secs. 27, 28, 33 & 34.	-250
	Land; surface very broken. Soil; 3rd rate and very stone. Good grass. Sec. 34 is very broken. There is about 30 acres of 1st rate bottom land along the creek; N.E. of creek, 3rd rate. S.W. of creek, 2nd rate. Sept. 5, 1878.	
	N. bet. Secs. 27 & 28. Var. 20°30'E.	
	Irregular S.W. face of bluff.	
30.00	Road, course E. & W.	
31.00	Ravine and spring.	
40.00	Set stone, 15 x 10 x 8 on S. hillside for $\frac{1}{4}$ Sec. Cor.	* 80
80.00	Set stone, 18 x 12 x 8 on S. side of rocky point for Cor. to Secs. 21, 22, 27 & 28. Cannot dig pits. I raise mound of stone around stake in lieu thereof. Set alder stake 2 ins. sq., 2 ft. long.	+150