

## Subdivisional Lines, T. 2 S., R. 30 E., W.M.

Chains		Feet
	Land; surface very broken. Soil; 3rd rate and very stony, some grass.	
	E. on random line bet; Secs. 22 & 27. Var. 20°E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.90	Intersected N. & S. line, 18 lks. N. of Cor. to Secs. 22, 23, 26 & 27, from which Cor. I run N.89°52' W. on a true line bet. Secs. 22 & 27. Var. 18°30'E.	
30.00	On ridge, course N. & S.	+ 80
40.45	Set stone, 20 x 12 x 10 on W. side of ridge for $\frac{1}{4}$ Sec. Cor.	30
47.00	Shallow ravine opens N.	- 50
61.00	Road, S.E. & N.W.	+ 50
80.90	The Cor. to Secs. 21, 22, 27 & 28. Land; surface hilly. Soil; 2nd and 3rd rate, good grass. S.W. $\frac{1}{2}$ of Sec. 27, very broken, 3rd rate land. N.E. $\frac{1}{2}$ , rolling 2nd rate land.	- 80
	N. bet. Secs. 21 & 22. Var. 20°E.	
9.00	Top of bluff.	+120
40.00	Set stone, 16 x 7 x 6 for $\frac{1}{4}$ Sec. Cor.	- 30
80.00	Set stone, 16 x 10 x 6 for Cor. to Secs. 15, 16, 21 & 22. Dug pits and set alder stake as per instructions. Land; surface on N. 71 chs., undulating on top of bluff, E. of creek. Soil; poor 3rd rate and stony, some grass.	
	E. on random line bet. Secs. 15 & 22. Var. 19°30'E.	
40.00	Set stake for temp. $\frac{1}{4}$ Sec. Cor.	
80.94	Intersected N. & S. line, 30 lks. N. of Cor. to Secs. 10, 11, 14 & 15, from which Cor. I run N.89° 47' W. on true line bet. Secs. 15 & 22.	