

Subdivisional Lines, T. 2 S., R. 30 E., W.M.

Chains		Feet
	bears N.10°W.	
80.94	The Cor. to Secs. 3, 4, 9 & 10. Land; surface S.60 chs. broken. Soil; 3rd rate, some grass. Sec. 3 is very broken, mostly 3rd rate, some 2nd rate on N. hillside, good bunch grass. Sept. 6, 1878.	+200
	N. bet. Secs. 32 & 33. Var. 20°42'E.	
25.00	Top of hill	+ 60
40.00	Set stone, 16 x 10 x 8 on N.E. hillside for $\frac{1}{4}$ Sec. Cor.	- 50
56.00	Road, E. & W.	- 80
58.00	Ravine, E.	- 20
80.00	Set stone, 18 x 10 x 7 for Cor. to Secs. 28, 29, 32 & 33. Dug pits and drove willow stake as per instructions. Land; surface rolling. Soil; 3rd rate, part 2nd rate, good grass.	
	E. on a random line bet. Secs. 28 & 33. Var. 20°30' E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.46	Intersected N. & S. line, 28 lks. N. of Cor. to Secs. 27, 28, 33 & 34, from which Cor., I run N.89°48' W. on a true line bet. Secs. 28 & 33. Var. 20°30' E.	
5.00	Foot of bluff	- 50
6.50	Creek, 25 lks. wide, course N.W.	
8.50	Road, N.W. & S.E.	
17.50	" N.E. & S.W.	
18.50	Spring branch, N.E.	
20.00	School-house bears S.5°W.	
20.00	John Gulliford's house bears S.15°W.	
40.23	Set stone, 14 x 12 x 5 for $\frac{1}{4}$ Sec. Cor.	+150
40.23	John Gulliford's house bears S.12°E. School-house bears S.76°E.	