

Subdivisional Lines, T.2 S., R.30 E., W.M.

Chains		Feet
80.46	<p>The Cor. to Secs. 28, 29, 32 & 33.</p> <p>Land; surface hilly.</p> <p>Soil; principally 2nd rate, small part on creek, 1st rate.</p> <p>Sec. 33, southern part rolling, northern part broken. There is good farming land in the southern part. Mr. Gulliford has about 100 acres in cultivation.</p>	+100
	<p>N. bet. Secs. 28 & 29.</p> <p>Var. 20°30' E.</p> <p>Along on ridge.</p>	
40.00	Set stone, 17 x 8 x 5 for $\frac{1}{4}$ Sec. Cor.	
80.00	<p>Set stone, 17 x 8 x 6 for Cor. to Secs. 20, 21, 28 & 29.</p> <p>Dug pits and drove willow stake as per instructions.</p> <p>Land; surface nearly level.</p> <p>Soil; 3rd rate. Good grass.</p>	
	<p>E. on random line bet. Secs. 21 & 28.</p> <p>Var. 21° E.</p>	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.54	<p>Intersected N. & S. line, 24 lks. S. of Cor. to Secs. 21, 22, 27 & 28, from which Cor., I run.</p> <p>N.(?) 89° 50' W. on a true line bet. Secs. 21 & 28,</p> <p>Var. 20° E.</p>	
29.50	<p>Foot of hill and fence N. & S.</p> <p>Wm. Stanton's house bears S. about 10 chs. dist.</p>	-300
34.00	Fence and creek, 28 lks. wide, runs N.	
35.00	Road, course N. & S.	
40.27	Set stone, 16 x 10 x 7 for $\frac{1}{4}$ Sec. Cor.	+ 50
80.54	<p>The Cor. to Secs. 20, 21, 28 & 29.</p> <p>Land; surface steep hillside, except creek bottom about 5 chs. wide.</p> <p>Soil; N. of creek 3rd rate, S. of creek 2nd rate, on creek 1st rate.</p> <p>Sec. 28 has about 80 acres of 1st rate bottom land, the remainder is steep hillside.</p>	+250