

Subdivisional Lines, T. 2 S., R. 30 E., W.M.

Chains		Feet
	N. bet. Secs. 20 & 21.	
	Var. 21° E.	
39.00	Ravine opens N.E.	-280
40.00	Set stone, 18 x 8 x 7 for $\frac{1}{4}$ Sec. Cor.	+ 12
52.50	John Molally's house bears S.67°E.	
60.00	" " " " S.48°E.	
72.00	Road and fence N.W. & S.E.	
80.00	Set stone, 12 x 10 x 8 for Cor. to Secs. 16, 17, 20 & 21.	
	Dug pits and drove willow stake as per instructions.	
	Land; surface broken.	
	Soil; 2nd rate, good grass.	
	<hr/>	
	E. on a random line bet. Secs. 16 & 21.	
	Var. 20°E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.48	Intersected N. & S. line, 38 lks. N. of Cor. to Secs. 15, 16, 21 & 22, from which Cor., I run N.89°54' W. on a true line bet. Secs. 16 & 21.	
	Var. 19°30'E.	
40.24	Set stone, 12 x 8 x 7 on N.W. hillside for $\frac{1}{4}$ Sec. Cor.	-100
68.00	Foot of bluff	-250
72.00	Creek, course N.	
80.48	The Cor. to Secs. 16, 17, 20 & 21.	+ 40
	Land; surface broken.	
	Soil; 3rd rate & 2nd rate and small part on creek, 1st rate.	
	Good grass.	
	Sec. 21 is very broken and has about 40 acres of 1st rate bottom land, remainder mostly 3rd rate.	
	Sept. 7, 1878.	
	<hr/>	
	N. bet. Secs. 16 & 17.	
	Var. 20°E.	
22.50	Creek bottom S.E. & N.W.	- 50
30.50	Leave creek bottom, N.E. & S.W.	
40.00	Set stone, 13 x 9 x 8 for $\frac{1}{4}$ Sec. Cor.	+ 40
56.00	Fence and road, N.E. & S.W.	