

## Subdivisional Lines, T. 2 S., R.30 E., W.M.

Chains		Feet
80.00	Set stone, 16 x 9 x 7 for Cor. to Secs. 8, 9, 16 & 17. Dug pits and drove willow stake as per instructions. Land; surface undulating. Soil; 2nd rate, creek bottom 1st rate. Good grass.	
	E; on random line bet. Secs. 9 & 16. Var. 19°30' E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.28	Intersected N. & S. line, 4 lks. N. of Cor. to Secs. 9, 10 & 16, from which Cor.; I run N.89°58' W. on a true line bet. Secs. 9 & 16. Var. 19°E.	
36.00	Ravine, course N.W. & S.E.	-250
40.14	Set stone, 17 x 10 x 5 for $\frac{1}{4}$ Sec. Cor.	+ 40
43.50	Road, course N.W. & S.E.	+ 30
66.00	Fence and creek bottom, N. & S.	-120
73.00	Creek, 30 lks., course N.	
78.00	Leave bottom	
80.28	The Cor. to Secs. 8, 9, 16 & 17. Land; surface broken. Soil; 2nd & 3rd rate, bottom 1st rate. Sec. 16 has about 40 acres of 1st rate bottom land, the rest is mostly 3rd rate.	+ 50
	N. bet. Secs. 8 & 9. Var. 19°30' E.	
20.00	Foot of hill	- 50
21.50	Creek, course N.E.	
33.00	Fence and road, N.E. & S.W.	
34.00	Rocky precipice, 20 ft. high, course N.E. & S.W.	
40.00	Set stone, 18 x 10 x 7 on S.E. hillside for $\frac{1}{4}$ Sec. Cor. Mrs. Nelson's house bears S.76°E.	+ 80
60.00	" " " " S.52°E.	
63.00	Top of bluff	+250
80.00	Set stone, 17 x 10 x 7 for Cor. to Secs. 4, 5, 8 & 9, dug pits and drove willow stake as per instructions.	