

Subdivisional Lines, T.2 S., R.30 E., W.M.

Chains		Feet
	Land; surface broken Soil; 3rd rate, on creek 1st rate. Willow and alder brush on creek. Mr. Nelson was killed by Indians in July.	
	<hr/>	
	E. on random line bet. Secs. 4 & 9. Var. 20° 45' E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.56	Intersected N. & S. line, 32 lks. S. of Cor. to Secs. 3, 4, 9 & 10, from which Cor. , I run N.(?)89°40'W. on a true line bet. Secs. 4 & 9. Var. 21°15'E.	
24.50	Foot of bluff, road and fence, course N.E. & S.W. Mr. Lightfoot's house bears S.74°W.	200
32.00	Creek, 30 lks. wide, course N.E.	
34.50	Foot of hill, leave bottom.	
40.28	Set stone, 20 x 12 x 4 for $\frac{1}{4}$ Sec. Cor. Mr. Lightfoot's house bears S.31°E.	100
80.56	The Cor. to Secs. 4, 5, 8 & 9 Land; surface very broken, except creek bottom, 1st rate. Some grass, willow and alder brush on creek. Sec. 9 is very much broken and is almost entirely 3rd rate land. This section contains about 80 acres of rich bot- tom land. Note: Near Mrs. Nelson's house is where Mr. Jewell was shot and wounded by Indians, of which he died.	200
	<hr/>	
	N. on a random line bet. Secs. 4 & 5. Var. 20°45'E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.86	Intersected N. Bdy., 132 lks. E. of Cor. to Secs. 4 & 5, from which Cor., I run S.57'E. on true line bet. Secs. 4 & 5. Var. 21°40'E.	
22.00	Ravine opens N.E.	80
40.86	Set stone, 20 x 9 x 7 on N. hillside for $\frac{1}{4}$ Sec. Cor.	60