

## Subdivisional Lines T.2 S., R.30 E., W.M.

Chains		Feet
80.86	The Cor. to Secs. 4, 5, 8 & 9 Land; surface considerably broken. Soil; 2nd & 3rd rate. Good grass. Sec. 4 has about 30 acres of rich bottom land, the remainder is principally 2nd rate and good for grazing. Sept. 9, 1878.	+ 20
	N. bet. Secs. 31 & 32. Var. 21°28' E.	
40.00	Set stone, 14 x 12 x 8 on W. hillside for $\frac{1}{4}$ Sec. Cor.	- 30
56.00	Jacob Stroud's house bears W. about 4 chs.	
61.00	Spring	
64.50	Spring branch, N.E.	- 80
67.00	Road, N.E. & S.W.	
80.00	Set stone, 20 x 10 x 7 on bench for Cor. to Secs. 29, 30, 31 & 32. Dug pits and drove willow stake as per instructions. Land; surface undulating. Soil; 2nd rate. Good grass.	+ 40
	E. on random line bet. Secs. 29 & 32. Var. 19° E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.20	Intersected N. & S. line, 38 lks. N. of Cor. to Secs. 28, 29, 32 & 33, from which Cor., I run N. 89°44' W. on a true line bet. Secs. 29 & 32. Var. 20°30' E.	
40.10	Set stone, 15 x 10 x 8 on W. hillside for $\frac{1}{4}$ Sec. Cor.	- 60
65.50	Brook, 4 lks. wide, N.W.	- 80
68.00	" " " " N.E.	
69.00	Road, course S.W. & N.E.	
80.20	The Cor. to Secs. 29, 30, 31 & 32. Land; surface rolling. Soil; 2nd rate, good grass. Sec. 32 is rolling and has some good farming land. There is one settler on this Sec., his house is not seen from line.	+ 40