

Subdivisional Lines, T. 2.S., R. 30 E., W.M.

Chains		Feet
	W. on random line bet. Secs. 30 & 31. Var. 19° E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
78.18	Intersected W. Bdy., 38 lks. N. of Cor. to Secs. 30 & 31, from which Cor., I run N. 89° 44' E. on a true line bet. Secs. 30 & 31. Var. 21° 35' E.	
38.18	Set stone, 15 x 12 x 10 on S.E. hillside for $\frac{1}{4}$ Sec. Cor.	60
66.56	Ravine, opens N.E.	80
78.18	The Cor. to Secs. 29, 30, 31 & 32. Land; surface broken. Soil; 3rd rate, good grass. Sec. 31 has about 100 acres of good farming land in the southern part, the remainder is rolling and good for grazing.	
	N. bet. Secs. 29 & 30. Var. 19° E. Along east hillside.	
34.50	Fence, course E. & W.	
40.00	Set stone, 24 x 12 x 10 for $\frac{1}{4}$ Sec. Cor.	
80.00	Set stone, 14 x 10 x 10 for Cor. to Secs. 19, 20, 29 & 30 Dug pits and drove willow stake as per instructions. Land; broken hillside. Soil; 2nd rate, good grass. A cabin on N.W. $\frac{1}{4}$ of Sec. 29 is not visible from line.	20
	E. on a random line bet. Secs. 20 & 29. Var. 22° 30' E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.42	Intersected N. & S. line, 68 lks. N. of Cor. to Secs. 20, 21, 28 & 29, from which Cor., I run N. 89° 31' W. on a true line bet. Secs. 20 & 29. Var. 21° E.	
40.21	Set stone, 14 x 12 x 7 for $\frac{1}{4}$ Sec. Cor.	30
65.50	Road and fence, N. & S.	180