

Subdivisional Lines, T. 2 S., R.30 E., W.M.

Chains		Feet
67.00	Brook, 8 lks. wide, course N.	
80.42	The Cor. to Secs. 19, 20, 29 & 30 Land; surface steep hillside. Soil; 3rd & 2nd rate, good grass. Sec. 29 has a narrow strip of bottom land from 2 to 4 chs. wide, extending through it. Remainder good for grazing.	+ 80
	W. on random line bet. Secs. 19 & 30. Var. 22° 30' E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
78.43	Intersected W. Bdy., 35 lks. N. of Cor. to Secs. 19 & 30, from which Cor., I run N.89° 45' E. on true line bet. Secs. 19 & 30. Var. 20° 15' E.	
38.43	Set stone, 17 x 8 x 5 for $\frac{1}{4}$ Sec. Cor.	+ 50
40.50	Fence and field, N. & S.	
50.00	Top of ridge, N.E. & S.W.	+100
74.00	Canyon opens N.E.	+150
78.43	The Cor. to Secs. 19, 20, 29 & 30. Land; surface broken. Soil; 2nd & 3rd rate. Good for grazing.	+ 80
	N. bet. Secs. 19 & 20. Var. 22°30' E.	
6.00	Ravine and spring branch N.E.	+ 80
14.00	Top of ridge, N.E. & S.W.	+100
40.00	Set stone, 16 x 12 x 4 for $\frac{1}{4}$ Sec. Cor. John Salisbury's house brs. N.20°W., 4.00 chs. dist.	-100
42.50	Fence, N.E. & S.W.	
48.50	Creek, 25 lks. wide, course N.E.	
57.00	Leave field, road N.E. & S.W.	
62.00	Foot of bluff, N.E. & S.W.	
80.00	Set stone, 18 x 10 x 8 for Cor. to Secs. 17, 18, 19 & 20 Dug pits, and drove willow stake as per instructions. Land; upland, broken- bottom, level. Soil; 3rd rate, bottom 1st rate & good for farming. Willow and alder on creek	+ 80