

## Subdivisional Lines, T.2 S., R.30 E., W.M.

Chains		Feet
	E. on random bet. Secs. 17 & 20. Var. 16° E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.68	Intersected N. & S. line, 42 lks. N. of Cor; to Secs. 16, 17, 20 & 21, from which Cor. , I run N.89° 42' W. on true line bet. Secs. 17 & 20. Var. 20° E.	
3.50	Fence and road, N. & S.	
25.00	Top of ridge, N. & S.	+180
40.34	Set stone, 14 x 9 x 5 for $\frac{1}{4}$ Sec. Cor.	- 40
66.50	Creek, 30 lks. wide, course N.E.	-150
68.50	Road, course N.E. & S.W.	
80.68	The Cor. to Secs. 18, 17, 19 & 20. Land; surface hilly, bottom level. Soil; bottom, 1st rate, remainder 3rd rate, good grass. Sec. 20 has about 20 acres of bottom land. Sept. 10, 1878.	+ 80
	W. on random bet. Secs. 18 & 19. Var. 16° E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
78.86	Intersected W. Bdy., 87 lks. N. of Cor; to Secs. 18 & 19, from which Cor., I run N.89° 23' E. on true line bet. Secs. 18 & 19. Var. 21° 46' E.	
9.50	Ravine opens S., spring	- 60
38.86	Set stone, 20 x 12 x 4 for $\frac{1}{4}$ Sec. Cor.	
78.86	The Cor, to Secs. 17, 18, 19 & 20 Land; surface very broken. Soil; 3rd & 2nd rate, good grass. Sec. 19 has about 40 acres of 1st rate bottom land, re- mainder mostly 3rd rate, some 2nd rate.	-300
	N. bet. Secs. 17 & 18. Var. 16° E.	
33.00	On spur	+150