

Subdivisional Lines, T.2 S., R.30 E., W.M.

| Chains | | Feet |
|---|---|------|
| 40.00 | Set stone, 14 x 12 x 4 for $\frac{1}{4}$ Sec. Cor. | + 20 |
| 54.00 | Ravine, course E. | -120 |
| 80.00 | Set stone, 19 x 10 x 8 for Cor. to Secs. 7, 8, 17 & 18. Dug pits and drove willow stake as per instructions. Land; surface very broken. Soil; poor 3rd rate, some grass. | +140 |
| <hr/> <p>E. on random line bet. Secs. 8 & 17. Var. 20° E.</p> | | |
| 40.00 | Set temp. $\frac{1}{4}$ Sec. Cor. | |
| 80.72 | Intersected N. & S. line, 50 lks. S. of Cor. to Secs. 8, 9, 16 & 17, from which Cor., I run S.89° 39' W. on true line bet. Secs. 8 & 17. Var. 19°30' E. | |
| 15.00 | Top of ridge, N.E. & S.W. | +120 |
| 32.50 | Creek, 20 lks. wide, course N.E. | -140 |
| 36.50 | Fence and road, course N.E. & S.W. | |
| 40.36 | Set stone, 15 x 8 x 5 under and against precipice, 20 ft. high for $\frac{1}{4}$ Sec. Cor. Charles R. Cote's house brs. S.5°W. | |
| 45.00 | " " " " " S.13°E. | |
| 80.72 | The Cor. to Secs. 7, 8, 17 & 18. Land; surface, broken. Soil; creek bottom 1st rate- remainder 3rd rate. Some grass. Willow and alder on creek. Sec. 17 contains about 30 acres rich bottom land. | +300 |
| <hr/> <p>W. on random line bet. Secs. 7 & 18. Var. 20°E.</p> | | |
| 40.00 | Set temp. $\frac{1}{4}$ Sec. Cor. | |
| 78.96 | Intersected W. Bdy., 12 lks. S. of Cor. to Secs. 7 & 18, from which Cor., I run S.89° 55' E. on a true line bet. Secs. 7 & 18. Var. 19° 40' E. | |
| 6.50 | Ravine opens N.E. | - 80 |
| 38.96 | Set stone, 18 x 10 x 4 for $\frac{1}{4}$ Sec. Cor. | + 30 |