

Subdivisional Lines, T.2 S., R.30 E.,W.M.

Chains		Feet
49.00	On table land	+ 60
74.00	Begin to descend	
78.96	The Cor. to Secs. 7, 8, 17 & 18.	- 60
	Land; surface some broken.	
	Soil; good 2nd rate, good grass.	
	Sec. 18 is about $\frac{1}{2}$ level table land and largest part of it is good for cultivation.	
<hr/>		
	N. bet. Secs. 7 & 8.	
	Var. 20° E.	
21.50	Ravine opens E.	-280
40.00	Set stone, 13 x 10 x 8 for $\frac{1}{4}$ Sec. Cor.	+280
80.00	Set stone, 16 x 10 x 8 for Cor. to Secs. 5, 6, 7 & 8.	- 50
	Dug pits and drove willow stake as per instructions.	
	Land; surface S. $\frac{1}{2}$ mile very broken- N. $\frac{1}{2}$ mile nearly level	
	Soil; S. $\frac{1}{2}$ mile 2nd rate, N. $\frac{1}{2}$ mile 3rd rate. Good grass.	
<hr/>		
	E. on random line bet. Secs. 5 & 8.	
	Var. 22° 15' E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.52	Intersected N. & S. line, 12 lks. N. of Cor. to Secs. 4, 5, 8 & 9, from which Cor., I run	
	N.89° 55' W. on true line bet. Secs. 5 & 8.	
	Var. 20° 45' E.	
33.00	Ravine opens S.	- 80
40.25	Set stone, 17 x 10 x 8 for $\frac{1}{4}$ Sec. Cor.	+ 20
56.00	Top of hill	+ 60
80.52	The Cor. to Secs. 5, 6, 7 & 8.	- 50
	Land; surface somewhat broken.	
	Soil; 3rd rate. W. 20 chs. good 2nd rate.	
	Sec. 8 is much broken, about 15 acres of creek bottom in S.E. Cor., and about 100 acres good upland in N.W. Cor.	
<hr/>		
	W. on random line bet. Secs. 6 & 7.	
	Var. 22° 15' E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	