

## Subdivisional Lines, T.2 S., R. 30 E., W.M.

Chains		Feet
79.38	<p>Intersected W. Bdy., 32 lks. N. of stone Cor. to Secs. 6 &amp; 7, from which Cor., I run N. 89° 46' E. on true line bet. Secs. 6 &amp; 7 Var. 22° 06' E.</p>	
39.38	Set stone, 18 x 10 x 7 for $\frac{1}{4}$ Sec. Cor.	30
68.00	Ravine opens N.E.	100
79.38	<p>The Cor. to Secs. 5, 6, 7 &amp; 8 Land; surface on W. <math>\frac{1}{2}</math> mile nearly level, E. <math>\frac{1}{2}</math> mile broken. Soil; mostly good 2nd rate, some on E. <math>\frac{1}{2}</math> mile 3rd rate. Sec. 7 is, about <math>\frac{1}{2}</math>, good wheat land and well adapted to cultivation.</p>	40
	<p>N. on random line bet. Secs. 5 &amp; 6. Var. 22° 15' E.</p>	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.54	<p>Intersected N. Bdy., 114 lks. E. of Cor. to Secs. 5 &amp; 6, from which Cor., I run S. 0° 49' E. on true line bet. Secs. 5 &amp; 6. Var. 21° E.</p>	
40.54	Set stone, 18 x 12 x 4 for $\frac{1}{4}$ Sec. Cor.	50
70.00	Ravine opens N.E.	80
80.54	<p>The Cor. to Secs. 5, 6, 7 &amp; 8 Land; surface broken by small ravines and ridges. Soil; principally 3rd rate, some 2nd rate, good grass. Sec. 5 is about <math>\frac{1}{2}</math> good for cultivation. Sec. 6 is about <math>\frac{1}{2}</math> good for farming. Sept. 11, 1878.</p>	60
	<b>General Description.</b>	
	<p>This township is prairie and has heretofore been classed as grazing lands, but from recent trials the larger part may be classed as agricultural. S. hillsides are generally very stony; N. hillsides and plateaus are free from stones and are rich deep soil and produce wheat and other grains.</p>	