

W. Bdy., Tp. 2 S., R. 31 E., W.M.

Chains		Feet
	Land; level. Soil; good 2nd rate. Very fine grazing.	
	S. on W. Bdy. Sec. 30. Var. 19°15' E.	
40.00	Set stone, 18 x 12 x 8 ins., for $\frac{1}{4}$ Sec. Cor.	
80.00	Set stone, 20 x 12 x 10 ins. for Cor. to Secs. 30, 31, 25 & 36. Land; level. Soil; 2nd rate.	
	S. on W. Bdy. Secs. 31. Var. 24° 30' E.	
40.00	Set stone, 22 x 8 x 6 ins. for $\frac{1}{4}$ Sec. Cor.	
80.00	Set post for Cor. to Tps. 2 & 3 S., Rs. 30 & 31 E., in mound of earth, with charred stake, pits, trench, etc. as per instructions. Land; level. Soil; good 2nd rate.	
<p>Exterior Lines, T. 2 S., R. 30<math>\frac{1}{2}</math> E., W.M. As surveyed by George S. Pershin, U.S. Deputy Surveyor. Under Contract. No. 313, Dated Dec. 7, 1878.</p> <p>*****</p> <p>I found all the Bdy. Cors. as represented in the field notes, furnished by the office, except the Cor. to Secs. 13 &amp; 24 on the E. Bdy.; and to re-establish this Cor.</p> <p>I begin at the Cor. to Secs. 24 &amp; 25 on the E. Bdy. and with with Burts Improved Solar Compass, I run N. along the range line on the E. Bdy. of Sec. 24. Var. 19° 15' E.</p> <p>80.00 Set post, 4 ins. sq., and 4 ft. long; raised mound, 4 ft. sq. and 2 ft. high for Cor. to Secs. 13, 24, 18 &amp; 19. This Cor. is on level plateau on fresh plowed ground and near the W. edge of same.</p> <p>Dec. 27, 1878.</p> <p>All stones used in marking Cors. in the above named Tp. are ferruginous basalt.</p>		