

Subdivisional Lines T.2 S., R.30 $\frac{1}{2}$  E., W.M.

Chains		Feet
	Var. 22° 50' E.	
11.60	The Cor. to Secs. 25 & 36, 26 & 35. Land; Surface west slope of hill. Soil; 2nd rate. Good grass.	
<hr/>		
	N. bet. Secs. 25 & 26.	
	Var. 20° 45' E.	
40.00	Set stone, 17 x 14 x 4 on N.W. slope of hill for $\frac{1}{4}$ Sec. Cor. 50	
65.00	George H. Piper's house brs. N.83° W., 3.50 chs. dist.	
66.00	Fence & field brs. E. & W.	
80.00	Set pine post, 4 ins. sq., and 4 ft. long, in plowed field for Cor. to Secs. 23, 24, 25 & 26. I did not dig pits or raise mound as they would be entirely useless. Land; surface undulating. Soil; 2nd & 1st rate, good grass, good for farming purposes.	
<hr/>		
	E. on random line bet. Secs. 24 & 25.	
	Var. 21° 30' E.	
40.00	Set post for Temp. $\frac{1}{4}$ Sec. Cor.	
79.82	Intersected E. Bdy., 82 lks. S. of stone Cor. to Secs. 24 and 25, from which Cor., I run S.89° 25' W. on true line bet. Secs. 24 & 25.	
	Var. 19° 15' E.	
32.50	Ravine opens N.	60
39.96	Set stone, 15 x 8 x 5 on N.E. slope for $\frac{1}{4}$ Sec. Cor.,	
55.00	On table land	60
60.00	Fence and field, course N. & S.	
79.82	The Cor. to Secs. 23, 24, 25 & 26. Land; surface undulating. Soil; 1st & 2nd rate, good grass, good for farming.	
<hr/>		
	W. on random line bet. Secs. 23 & 26.	
	Var. 21° 30' E.	
11.68	Intersected W. Bdy., 20 lks. N. of stone Cor. to Secs. 23 and 26, from which Cor., I run N.89° 00' E. on true line bet. Secs. 23 & 26.	