

Subdivisional Lines T.2 S., R.30 $\frac{1}{2}$ E., W.M.

Chains		Feet
	Var. 20°04' E.	
5.50	Road & fence, course N. & S.	
11.68	The Cor. to Secs. 23, 24, 25 & 26. Land; surface rolling. Soil; 1st & 2nd rate, good grass, well adapted to farming. Dec. 26, 1878.	
N. bet. Secs. 23 & 24.		
	Var. 21° 30' E.	
20.00	Fence and road, course N.20°E. and S.20° W.	
40.00	Set stone, 18 x 14 x 5 on E. hillside in mound of stone for $\frac{1}{4}$ Sec. Cor.	+ 40
55.00	Henry Hewett's house brs. N.77° E.	
60.00	" " " " S.66° E.	
69.00	Ravine opens N.W.	- 60
80.00	Set stone, 17 x 14 x 4 for Cor. to Secs. 13, 14, 23 & 24 drove stake in pits S.E. of Cor. and raised mound of stone in lieu of other pits. Land; surface rolling. Soil; 1st & 2nd rate, good grass, good for farming.	+ 60
E. on random line bet. Secs. 13 & 24.		
	Var. 20° E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
79.62	Intersected E. Bdy., 48 lks. S. of post Cor. to Secs. 13 and 24, from which Cor., I run S.89° 39' W. on true line bet. Secs. 13 & 24. Var. 19° E.	
39.81	Set stone, 15 x 10 x 10 on S.W.slope in mound of stone for $\frac{1}{4}$ Sec. Cor.	
44.00	Road, course N.E. & S.W.	
79.62	The Cor. to Secs. 13, 14, 23 & 24. Land; surface E. $\frac{1}{2}$ mile level, W. $\frac{1}{2}$ mile rolling. Soil; E. $\frac{1}{2}$ mile level, W. $\frac{1}{2}$ mile 2nd rate. Good grass, good for farming. The Cor. of Sec. 13 & 24 on E. Bdy. was obliterated and	- 50