

Exterior Bdys. T. 2 S., R. 31 E., W.M.

| Chains | | Feet |
|---------------------------|--|-------|
| 80.00 | Set post, for Cor. to Secs. 2, 3, 34 & 35, in mound of earth, with charred stake, pits, trench, etc., as per instructions. Land; very rough and broken. Soil; 3rd rate. Oct. 4, 1864. | +200 |
| E. on S. Bdy. of Secs. 35 | | |
| Var. 22° E. | | |
| 15.00 | Top of hill, brs. N. & S.. Descend. | + 200 |
| 40.00 | Set stone, 24 x 15 x 8 ins., for $\frac{1}{4}$ Sec. Cor. | -200 |
| 45.00 | Foot of hill. Ascend. | |
| 80.00 | Set stone, 36 x 8 x 8 ins., for Cor. to Secs. 1, 2, 35 & 36. Land; hilly. Soil; 2nd rate. | + 500 |
| E. on S. Bdy. of Sec. 36. | | |
| Descend hill. Var. 21° E. | | |
| 24.15 | Foot of hill. Brook, 4 lks., course N. Ascend hill. | - 600 |
| 40.00 | Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, trench, etc., as per instructions. | |
| 62.00 | Top of hill, brs. N. & S. Descend. | + 700 |
| 80.00 | Set post for Cor. to Tps. 2 & 3 S., Rs. 31 & 32 E., in mound of earth, with charred stake, pits, trench, etc., as per instructions. Land; hilly. Soil; 2nd rate. Fine grass. | |
| N. on E. Bdy. of Sec. 36. | | |
| Descend hill. Var. 19° E. | | |
| 21.25 | Deep canyon and creek, 6 lks. wide, runs N. Ascend hill. | - 600 |
| 40.00 | Set stone, 24 x 6 x 6 ins., for $\frac{1}{4}$ Sec. Cor. Top of hill on W. slope. Descend. | + 600 |
| 80.00 | Set stone, 18 x 15 x 8 ins., for Cor. to Secs. 30, 31, 25 and 36. | - 600 |