

Subdivisional Lines, T. 2 S., R. 31 E., W.M.

Chains		Feet
	E. on random line bet. Secs. 25 & 36.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.80	Intersected E. Bdy., 70 lks. S. of Cor. to Secs. 25 & 36, from which Cor., I run S. 89° 30' W. on true line bet. Secs. 25 & 36. Descend hill.	
10.00	Foot of hill, brook, 6 lks. wide, runs N.W. Ascend hill.	+100
33.00	Top of hill, hrs. N. & S. Descend.	+600
40.40	Set stone, 20 x 10 x 8 for $\frac{1}{4}$ Sec. Cor.	
80.80	The Cor. to Secs. 25, 26, 35 & 36. Land; hilly. Soil. 3rd rate.	+400
	N. bet. Secs. 25 & 26. Ascend hill. Var. 20° E.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, etc., as per instructions. Top of hill. Descend.	+200
80.00	Set post for Cor. to Secs. 23, 24, 25 & 26, in mound of earth, with charred stake, pits, etc., as per instruct- ions. Land; hilly. Soil; 2nd rate.	+350
	E. on random line bet. Secs. 24 & 25.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.67	Intersect E. Bdy., 57 lks. S. of Cor. to Secs. 24 & 25, from which, I run S. 89° 36' W. on true line bet. Secs. 24 & 25. Ascend hill.	
35.00	Top of hill, hrs. N. & S. Descend.	+300
40.33	Set stone, 15 x 8 x 8 for $\frac{1}{4}$ Sec. Cor.	
50.00	Foot of hill. Ascend.	+250
80.67	The Cor. to Secs. 23, 24, 25 & 26. Land; hilly. Soil; 2nd rate.	+200
	N. bet. Secs. 25 & 24. Var. 20° E.	