

7.

Subdivisional Lines, T. 2 S., R. 31 E., W.M.

Chains		Feet
	Descend hill.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, etc., as per instructions.	
80.00	Set stone, 18 x 12 x 5 for Cor. to Secs. 13, 14, 23 & 24. Land; rolling Soil; good 2nd rate.	-35
<hr/>		
	E. on random line bet. Secs. 13 & 24.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.42	Intersect E. Bdy., 34 lks. S. of Cor. to Secs. 13 & 24, from which Cor., I run S.89° 45' W. on true line bet. Secs. 13 & 24. Ascend hill.	
40.21	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, etc., as per instructions.	
80.42	The Cor. to Secs. 13 & 24, 14 & 23. Land; hilly. Soil; 2nd rate.	+40
<hr/>		
	N. bet. Secs. 13 & 14. Descend hill. Var. 21° E.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound of earth, with charred stake, pits, etc., as per instructions.	
80.00	Set post for Cor. to Secs. 11, 12, 13 & 14, in mound of earth, with charred stake, pits, etc., as per instructions. Land; rolling. Soil; good 2nd rate.	-30
<hr/>		
	E. on random line bet. Secs. 12 & 13.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.38	Intersect E. Bdy., 38 lks. S. of Cor. to Secs. 12, & 13, from which, I run S.89° 44' W. on true line bet. Secs. 12 & 13. Descend hill.	
40.19	Set stone, 20 x 12 x 4 for $\frac{1}{4}$ Sec. Cor.	
71.00	Brook, 6 lks. wide, runs N.W.	-40
75.00	Road brs. N.W. & S.E.	
80.38	The Cor. to Secs. 11, 12, 13 & 14. Land; hilly. Soil; 2nd rate.	