

Subdivisional Lines, T.2 S., R.31 E., W. M.

Chains		Feet
80.20	The Cor. to Secs. 1, 2, 11 & 12. Land; hilly. Soil; good 2nd rate.  Nov. 18, 1864.	400
<hr/>		
	N. bet. Secs. 34 & 35. Descend hill.	
16.00	Foot of hill. Ascend	150
40.00	Set stone, 18 x 12 x 8 for $\frac{1}{4}$ Sec. Cor.	
80.00	Set stone, 18 x 14 x 5 for Cor. to Secs. 34, 35, 26 & 27. Land; hilly. Soil; good 2nd rate.	400
<hr/>		
	E. on random line bet. Secs. 26 & 35.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.50	Intersect N. & S. line at Cor. to Secs. 25, 26, 35 & 36, from which, I run W. on true line bet. Secs. 26 & 35. Descend hill.	
15.00	Brook, 5 lks. wide, runs N.	250
39.75	Set stone, 24 x 12 x 8 for $\frac{1}{4}$ Sec. Cor.	
40.00	Foot of hill. Ascend.	
79.50	The Cor. to Secs. 26, 27, 34 & 35. Land; hilly. Soil; 2nd rate.	450
<hr/>		
	N. bet. Secs. 26 & 27. Descend hill. Var. 21° E.	
40.00	Set stone, 20 x 12 x 5 for $\frac{1}{4}$ Sec. Cor.	
47.50	Ravine brs. N.E.	
80.00	Set post for Cor. to Secs. 22, 23, 26 & 27, in mound of earth, with charred stake, pits, etc., as per instructions.  Land; hilly. Soil; 2nd rate.	
<hr/>		
	E. on random line bet. Secs. 23 & 26.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
79.70	Intersect N. & S. line at Cor. to Secs. 23, 24, 25 & 26, from which Cor., I run	