

## Subdivisional Lines, T. 2 S., R.31 E., W.M.

Chains		Feet
	Land; rolling. Soil; 2nd rate.	
	N. bet. Secs. 9 & 10.	
30.00	Ascend hill. Var. 18° E. Top of hill	+ 500
40.00	Set stone, 18 x 12 x 4 for $\frac{1}{4}$ Sec. Cor.	
80.00	Set stone, 16 x 8 x 6 for Cor. to Secs. 3, 4, 9 & 10. Land; rolling. Soil; good 2nd rate.	
	E. on random line bet. Secs. 3 & 10.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.22	Intersect N. & S. line at Cor. to Secs. 2, 3, 10 & 11, from which, I run	
	W. on true line bet. Secs. 3 & 10. Ascend hill.	
40.11	Set stone, 14 x 10 x 6, for $\frac{1}{4}$ Sec. Cor.	
80.22	The Cor. to Secs. 3, 4, 9 & 10. Land; rolling. Soil; good 2nd rate.	+ 500
	N. on a random line bet. Secs. 3 & 4.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor. Var. 19° E.	
80.41	Intersect N. Bdy., 21 lks. W. of Cor. to Secs. 3 & 4, from which Cor., I run	
	S.0°9' W. on true line bet. Secs. 3 & 4.	
40.41	Set stone, 14 x 10 x 6, for $\frac{1}{4}$ Sec. Cor.	
80.41	The Cor. to Secs. 3, 4, 9 & 10. Land; gently rolling. Soil; good 2nd rate.	
	N. bet. Secs. 32 & 33..	
5.00	Ravine brs. N.W. Ascend.	
30.00,	Top of hill brs. E. & W. Descend.	
40.00	Set stone, 18 x 8 x 8 for $\frac{1}{4}$ Sec. Cor.	
80.00	Set post for Cor. to Secs. 28, 29, 32 & 33, in mound of earth, with charred stake, pits, etc., as per instruct- ions. Land; hilly. Soil; 2nd rate.	